

#### **Rialtas na hÉireann** Government of Ireland



# Ireland National Report



## Irish GNSS Network

Currently 27 operational stations

25 Leica GR30 receivers / AR10 antenna

2 Leica GR50 receivers / AR20 antenna

1 planned station this year GR50/AR20

1 old station to remove





# **Bedrock Stations**

Last update in 2019 we were working towards 3 bedrock stations

- Valentia is upgraded and operational
  EPN station
- Malin Head is up and running proposed to join EPN network
   Part of the SONEL project
- Mace Head is in the final stages and we hope to be up and running by the end of the summer.





# **Absolute Gravity Network**

#### Planned AGN for Ireland

- Approx 50 points
- On bedrock if possible
- Joint project with LPS







### **Absolute Gravity Network**

#### Progress to date:

- On hold due to Covid 19 restrictions
- Hoping to restart
- Tidal gravimeter ran for much longer than planned.







## Levelling network expansion

As part of the AGN new levelling was required.

- Extensive levelling campaign for AGN
- Great opportunity to assess our Geoid Model





